LUMINAIRE SCHEDULE FOR CONTACTOR CABINET @ _____ STA. CABINET #_____

COB POLE NO.*	LUM. NO. ⬡	CIRCUIT NO.	STATION (OFFSET)	TYPE–DISTRIBUTION –WATT	POLE HEIGHT	POLE TYPE	COMMENTS
NE 8@100–01	1	1	12+73 (38 LT)	COBRAHEAD MC III 250 HPS	35'	DAVIT	
EGATE@139–06	2	2	14+05 (30 RT)	SHOEBOX MC II 250 HPS	12.2 m	EXPOSED AGGREGATE	
	3						
	4						
	5						

* ASSIGNED BY C.O.B. SIGNAL & LIGHTING ENGINEER.

ILLUMINATION WIRE SCHEDULE

RUN NO. △	CONDUCTORS	CONDUIT
1	2#8 (ILL.), 2#8 (REC.), 1#8 (GROUND)	2"
2	4#8 (ILL.), 2#8 (REC.), 1#8 (GROUND)	2"
3		
4		
5		

ILL. = ILLUMINATION
REC. = RECEPTACLES

City of Bellevue

LUMINAIRE SCHEDULE AND ILLUMINATION WIRE SCHEDULE

DRAWING NUMBER	TSSL–4
SCALE	NONE
REVISION DATE	11/12
DEPARTMENT	TRANS