



NOTES:

1. ALL PIPE STAKES, HARDWARE AND MATERIALS SHALL BE HOT DIPPED GALVANIZED AFTER FABRICATION.
2. TYPE 1 PIPE STAKE: 2" O. D. GALVANIZED PIPE, 6' LONG, WITH A 2" O. D. THREADED PIPE CAP OR WELDED COLLAR. THE OTHER END IS TO BE FLATTENED OR CUT TO TO A POINT.
3. ANCHOR ASSEMBLY IS AN ALTERNATE TO S-19 (BURIED PIPE) OR FOR ABOVE GROUND PIPE WHERE APPROVED BY THE CITY.

	<p style="font-size: 24pt; margin: 0;">City of Bellevue</p>	<p>SEWER UTILITIES</p>
<p>TITLE</p> <p style="font-size: 18pt; margin: 0;">PIPE STAKE ANCHOR ASSEMBLY</p>		
<p>JANUARY 2009</p>		<p>NO. S-20</p>