Bellevue Way SE HOV – 112th Ave SE 'Y' to South Bellevue P&R Staff recommendation

January 25th, 2018 – Transportation Commission

```
Presenter:
Marina Arakelyan, Project Manager, City of Bellevue
Email: <u>Marakelyan@bellevuewa.gov</u>
Phone: 425-452-4632
```

Tonight's Agenda:

- Project status
- Construction phasing and associated cost
- Implementation options and b/c analysis
- Staff recommendation
- Comments and questions
- Motion to Approve Staff Recommendation
- Next Step



Project Status:

- Project Scope approved by City Council on April 6,2017
- Completed 30% design and prepared environmental documentation
- Continue engaging with community and stakeholders
- Developed construction phasing and associated cost
- Developed project implementation options

Bellevue Way SB HOV Project – Approved Project Scope



- Improve multi-modal access
- Encourage mode shift to HOV/Transit

Ave

2H

SE 30th

Bellevue Way SB HOV Project -Construction Phasing and Costs



	Design Costs	ROW Costs	Construction Costs	Total Costs
Phase A	\$1,200,000	\$1,900,000	\$5,500,000	\$8,600,000
Phase B	\$2,000,000	\$2,400,000	\$9,200,000	\$13,600,000
Phase C	\$800,000	\$5,700,000	\$3,700,000	\$10,200,000
Phase D	\$350,000	\$0	\$1,700,000	\$2,050,000

Bellevue Way SB HOV Project-Implementation Options and Cost



Implementation Option Comparison – Throughput & Travel Time Savings

	2015 Existing Conditions	2030 Baseline No Build	Option A: 320-ft HOV	Option A +B: HOV to Winters House	Option A+B+C: HOV through "Y" 112th only	Option A+B+C+D: HOV through "Y" 112th and BWSE to 108th	
Southbound Thre	oughput from Bo	oth Directions (Bellevue Way and	112th Ave)			
Vehicles	2,303	2,163	2,242	2,433	2,456	2,469	
People	2,665	3,876	3,966	4,405	4,483	4,496	
Bellevue Way SE Travel Time (Min/Veh)			Travel Time Savings compared to 2030 Baseline (Min/Veh)				
SOV	5.6	7.5	-0.5	-0.9	0.1	0.2	
HOV	5.6	7.2	-1.0	-2.5	-3.0	-3.1	
Transit	5.7	6.7	-0.6	-1.9	-2.5	-2.7	
112th Ave SE Travel Time (Min/Veh)			Travel Time Savings compared to 2030 Baseline (Min/Veh)				
SOV	7.6	9.9	-0.6	-0.9	0.4	0.9	
HOV	7.6	9.5	-1.0	-2.6	-4.0	-3.6	
Transit	6.2	10.6	-1.0	-2.2	-3.7	-3.5	

Note: for PM Peak Hourly

Implementation Option Comparison – Annual Delay and Travel Time Savings (\$)

	2015 Existing Conditions	2030 Baseline No Build	Option A: 320-ft HOV	Option A +B: HOV to Winters House	Option A+B+C: HOV through "Y" 112th only	Option A+B+C+D: HOV through "Y" 112th and BWSE to 108th
Annual Cost of Delay for all users*			Annual Travel Time Savings for all users over 2030 Baseline*			
Time in \$	\$2,975,201	\$6,602,836	\$758,001	\$2,031,800	\$2,138,645	\$1,999,954

Annual Cost of Delay = (Congested Travel Time – Free Flow Travel Time) * Value of Time

Annual Travel Time Savings = (Option Travel Time – No Build Travel time)* Value of Time

- Time savings reflect cumulative benefit for all modes for each Option
- Vehicle Occupancy: SOV = 1 person/veh, HOV = 2.2 persons/veh, Transit = 75 persons/bus
- Value of Time: \$22/hour (2018 dollars)
- Travel time savings from 3 hour PM peak period (260 working days/year)
- Annual cost of person delay is projected to double from 2015 to 2030
- Annual travel time savings used to develop Benefit/Costs of possible phasing options

Implementation Option Comparison-Benefit / Cost

	Options	Cumulative Costs		Annual Value of Travel Time Savings	Benefit / Cost Ratio (ex. 10-yr duration)	
	A —	\rightarrow	\$8,600,000	\$758,000	0.88	
	A+B —	\rightarrow	\$22,200,000	\$2,031,800	0.91	
	A+B+C	\rightarrow	\$32,400,000	\$2,138,645	0.65	
A	A+B+C+D -	\rightarrow	\$34,450,000	\$1,999,954	0.57	

- Option A+B has the highest B/C ratio
- Option A+B+C has the the highest annual travel time saving but lower B/C ratio
- Option A+B+C+D and Option A+B+C has similar levels of person throughput but lower overall travel time savings than Option A+B+C.

Bellevue Way SE HOV – 112th Ave SE 'Y' to South Bellevue P&R

Staff recommendation:

 Full Implementation of Option A+B
 Defer Phase C and D Implementation for future years



Bellevue Way SE HOV – 112th Ave SE 'Y' to South Bellevue P&R

Comments and Questions?

Motion to APPROVE staff recommendation:

 Full Implementation of Option A+B
 Defer Phase C and D Implementation for future years



Bellevue Way SE HOV – 112th Ave SE 'Y' to South Bellevue P&R

NEXT STEP:

Seek City Council approval of staff recommendation on February 20th, 2018

Thank You!

Contact Information:

Marina Arakelyan, project manager Marakelyan@bellevuewa.gov; ph. 425-452-4632