



NOTES:

1. REPLACE ANY EXISTING 4" SIDE SEWER WITH 6" PVC AND TO EXTEND TO THE EDGE OF RIGHT-OF-WAY. REMOVE AND DISPOSE OF ANY EXISTING PIPE THAT IS NOT REUSED.
2. RELOCATE SIDE SEWER ONLY WHERE REQUIRED BY ROADWAY CUT.
3. CONNECT TO EXISTING SIDE SEWER AND MAIN LATERAL WITH MECHANICAL COUPLINGS (SEE APPROVED MATERIALS LIST)
4. MECHANICAL TRANSITION COUPLING (SEE APPROVED MATERIAL LIST)



City of
Bellevue

SEWER UTILITIES

TITLE

SIDE SEWER LATERAL RELOCATION